Item	Unit	Rate
Earthwork		
Earthfill (dams, basins)	cubic yard	$4.70
Earthmoving (terraces)	linear foot	$6.15
Waterway Shaping	acre	$5,922.50
Erosion Control for Grassed Waterways		
Fabric Checks	foot	$3.45
Mulching	acre	$5,750.00
Subsurface Drainage Tile		
4-inch Tile	foot	$2.55
5-inch Tile	foot	$2.90
6-inch Tile	foot	$3.65
8-inch Tile	foot	$5.20
10-inch Tile	foot	$7.80
12-inch Tile	foot	$10.15
Tile Hook-ups	10% of total linear tile cost budgeted	
Tile Intakes		
5-inch Intake	each	$276.00
6-inch Intake	each	$310.50
8-inch Intake	each	$379.50
Tile Outlets		
6-inch Outlet	each	$253.00
8-inch Outlet	each	$345.00
10-inch Outlet	each	$379.50
12-inch Outlet	each	$488.75
15-inch Outlet	each	$586.50
18-inch Outlet	each	$701.50
Grade Stabilization Structure Components (PS = Principal Spillway)		
6-inch PS Pipe	foot	$40.25
8-inch PS Pipe	foot	$57.50
10-inch PS Pipe	foot	$63.25
12-inch PS Pipe	foot	$74.75
14-inch PS Pipe	foot	$80.50
16-inch PS Pipe	foot	$97.75
Fence *	foot	$2.90
Livestock Pipeline *	foot	$2.05
Hydrant *	each	$379.50
Livestock Watering Tank *	each	$1,437.50
Heavy Use Area Protection (pad for tank) *	square foot	$1.75
Tree Clearing (site prep for dams only) *	acre	$2,300.00
Seeding		
Critical Area Planting	acre	$460.00
Conservation Cover - Introduced Species	acre	$391.00
Conservation Cover - Native Species	acre	$500.25

*Indicates optional components of grade stabilization structures.

NOTE: County Average Rates are used for estimates for State Cost Share projects. Landowners are encouraged to contact contractors for quotes.